BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT32226

APPROVED SCHEDULE - B

E/BTP/BBMP/E-PMT/12/2018-19, Date: 22.11.2018

Construction of RCC drains in Ramachandrapura Slum Main Road Ward No10 Vidyaranyapura Sub-divison

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N M SHIVAKUMAR ( )	
				In Figures	In Words
1	211.95	KSRRB M200-12.3. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. C. Prestressed / Reinforced cement concrete grade M-20 & above. MORTH Specification No. 202 Page No. 137 / Item No. 18.19, PWD SR 2016-17	Cum	1000.0	Rupees One Thousand Only
2	428.22	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 Page No. 142 / Item No. 19.1, PWD SR 2016-17	Cum	199.0	Rupees One Hundred Ninety Nine Only
3	164.15	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 Page No. 23 / Item No. 5.9, PWD SR 2016-17	Cum	4800.0	Rupees Four Thousand Eight Hundred Only
4	1427.4	KSRB 15.1.3 Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications Page No. 113 / Item No. 15.3, PWD SR 2016-17	Sqm	103.0	Rupees One Hundred Three Only
5	71.37	KSRB 4-1.6 : Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2. No. 12/ Item No. 4.6 / PWD SR 2016-17	Cum	5000.0	Rupees Five Thousand Only
6	1427.4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete7.5 cms thick Page No. 25 / Item No. 5.31.1/ PWD SR 2016-17	Sqm	665.0	Rupees Six Hundred Sixty Five Only
7	6344	KSRB 5-9: Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded) KBS 5.1.13 Page No. 24 / Item No. 5.22 / PWD SR 2016-17	Sqm	37.0	Rupees Thirty Seven Only
8	1427.4	KSRB 5-8.2 : Providing two line dressing to granite stone slab / granite stone masonry as per specifications. KBS 5-1.13 Page No. 24 / Item No. 5.18 / PWD SR 2016-17	Sqm	780.0	Rupees Seven Hundred Eighty Only
9	1762	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete Page No. 25 / Item No. 5.30 PWD SR 2016-17	No	331.0	Rupees Three Hundred Thirty One Only
10	356.85	KSRB 15-19.1 : Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. Page No. 122 / Item No. Item No. 15.80, PWD SR 2016-17	Sqm	27.0	Rupees Twenty Seven Only

Signature of the contractor

30/01

Executive Engineer

	oved Qty.	Description	Unit	Approved Tender Rates of N M SHIVAKUMAR ( )	
				In Figures	In Words
11	356.85	KSRB 15-19.2 : Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.Page No. 122 / Item No. Item No. 15.81, PWD SR 2016-17	Sqm	69.0	Rupees Sixty Nine Only

Signature of the Contractor

30/01

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

30/01